



CAMPDEN HILL



SHELDRAKE PLACE

INTERLOCK SEALING DETAIL (Grade 2 Basement Wall).



NOTES

- See also SPUK Installation Method Statement & Sheets SEQ/1 to SEQ/4 for proposed Sequence of Works.
- NB/ 'Dummy Piles' & Step Up/Down details to facilitate the GIKEN Pile Press are not shown.
- Machine step positions to be checked as work progresses and are to be to match the sequence of work.
- For SPUK Sheets for Sections S/1, S/2, S/3 & S/4.
- For Watertight Sections & Elevations - See dgs. P011, P012 & P014.
- For Watertight Piling Platform Levels, Ramp Details & Initial Bulk Earthworks - See McGee Piling Platform Sketch Drawings.
- Setting Out by Others - The coordinates to the face of the sheet pile lines are given on Watertight dgs. SP01 & SP02.
- Pile numbers, wall plan lengths, pile orientations and corner configurations indicated are indicative only and are subject to rolling / installation tolerances and pile care changes.
- Interlocking corners (Type E20) are to be used at all corners. Following the corner installation, the proximity to the theoretical corner setting out is to be assessed and the sheet piles shall be 'cranked' as required (max. 5 degrees per interlock) to re-establish as near as is possible the theoretical setting out lines (front face of sheet piles). See Detail 1.
- Notwithstanding the above, the achievable sheet pile layout will be a 'best-fit' layout, within the constraints of the GIKEN installation methodology.
- Installation is generally subject to SPUK's standard tolerances of +450mm in Plan Position at the command level & 1 in 75 vertically. Unless noted otherwise, the Sheet Piles are generally to be installed to the 'Top Levels' (TOSP), given, which are the final levels prior to RC Capping Beam construction. Where required, due to external levels, an initial bulk excavation is to be carried out to provide Platform Levels - Details TBC.
- The Sheet Pile interlocks from top level to formation level to be plated and welded with non-structural 6mm sealing welds to achieve a BS8102 Grade 2 Basement. - See Detail 1.
- SPUK's standard tolerances of +450mm in Plan Position at the command level & 1 in 75 vertically. Unless noted otherwise, the Sheet Piles are generally to be installed to the 'Top Levels' (TOSP), given, which are the final levels prior to RC Capping Beam construction. Where required, due to external levels, an initial bulk excavation is to be carried out to provide Platform Levels - Details TBC.
- Where possible the RC capping beams are to be constructed prior to bulk excavation of the basement. Capping Beam SS's vary - see relevant Watertight drawings.
- Temporary Support to sheet piles (Walings & Props at 2 levels) is required where indicated - Details TBC.

SHEET PILES : (All Quantities Approximate) :-

- 421 no. ARCELOR GU 18N (S355GP) - or similar approved
- 254 no. @ 10.0m
- 112 no. @ 12.0m
- 55 no. @ 12.5m
- 196 no. ARCELOR GU 23N (S355GP) - or similar approved
- 95 no. @ 12.0m
- 72 no. @ 14.0m
- 23 no. @ 12.0m (Temporary / Sacrificial Sheet Piles)
- Total Number of Sheet Piles = 617 no.

KEY :

TOSP = FINAL TOP OF SHEET PILE LEVEL
TL = PILE TOP LEVEL

REF	CDM (2017) - RESIDUAL RISKS
01	Safe Storage & Site Access different to design assumptions.
02	Obstructions along the sheet pile lines.
03	Excavations along the sheet pile lines.
04	Excessive Surcharge Loadings.
05	Excessive Accidental Overdig (above Allowance in Design).
06	Stability Services crossing sheet pile lines.
07	Degradation / weakening of passive formation.
08	Actual load capacity of installed sheet piles.

FOR CONSTRUCTION



Office: House, Rough Hay Road,
Gillingham, Faversham, ME13 9AR
Telephone: 01772 794141
Email: enquiries@sheetpilinguk.com
web: www.sheetpilinguk.com

Project:	CAMPDEN HILL :- BASEMENT.
Client:	McGEE GROUP LTD.
Drawn By:	08/08/14
Checked By:	FOR CONSTRUCTION - TEMP. / SACRIFICIAL PILES ADDED.
Issue:	24/07/14
Issue:	FIRST ISSUE FOR REVIEW
Issue:	GAP

Scale:	Shown
Scale:	G.P.Oils
Scale:	AJC
Scale:	A